OCPP 1.6
Full Certificate

OCPP 1.6 Fully Certified

Certificate holder:	MODERNTEC Co., Ltd
Certificate number:	OCA.0016.0425.CS
Product type:	Charging Station
Product designation:	MC-IN60-1A-C OCPP Software version: 1.0.0 Hardware feature set as stated below
Certification date:	July 13, 2023

This certificate attests that the above mentioned product successfully completed certification testing in conformance with the reference specification OCPP 1.6 – Edition 2 with OCPP 1.6 Errata sheet (v4.0 Release, 2019-10-23). The optional features of the protocol are also covered by this certification.

Test cases have been performed as described in the test report referred to below. The results and remarks can be found in the complete test report.

Applied tests	Performed by / on	Document evidence
Conformance testing according to the test specification referenced by the test report	*Korea Smart Grid Association,* *July 13, 2023*	*(KSGA)Moderntec_Test Report template_MC-IN60-1A-C_230713*

The abstract of test report in the Annex is an integral part of this certificate. This certificate is valid from the Certification Date specified above. This certificate is only applicable to the product designation described above and permits the use of the OCPP logo as laid down in the OCA certification logo license agreement on this product only.

This certificate shall neither be tendered nor accepted by any party as a guarantee covering quality of a product which includes OCPP. The Open Charge Alliance, and/or its agents, including, inter-alia, test laboratories, disclaim liability for any damages or losses incurred by the certified company or by any other party resulting from reliance on the results of OCPP certification testing.

For the Open Charge Alliance:

ONOPH CARON
Chairman

Abstract of test report

Test Result Summary

Test Report OCPP 1.6 Certification	
Test laboratory:	**Korea Smart Grid Association**
Location:	Seoul , Korea
Test Report Reference:	KSGA-OCPP1.6TEST-127-2023
Vendor name:	**MODERNTEC Co., Ltd**
Device Under Test:	Charging Station
Communication:	JSON
OCPP Software version:	1.0.0

Test Result Summary for the certified functionalities		
Functionalities	**OCPP 1.6 Certification Test Results**	**Description**
Core	Pass	Basic Charging Station functionality for booting, authorization (incl. cache if available), configuration, transactions, remote control.
Optional features		
Firmware Management	Pass	Support for (remote) firmware update management and diagnostic log file download.
Smart Charging	Pass	Support for Smart Charging (all profile types, including stacking), to control charging.
Reservation	Pass	Support for reservation of a connector of a Charging Station.
Local Authorization List Manageme	Pass	Features to manage a local list in the charging station containing authorization data for whitelisting users.
Remote Trigger	Pass	Support for remotely triggering messages that originate from a Charging Station. This can be used for resending messages or for getting the latest information from the Charging Station.

Performance Measurement Results

Name	PICS value	Measured value	Description
OCPP triggered function timeout:	30s	00:00:19	The response time for when waiting for an OCPP function with its corresponding request message. (Firmware update, Diagnostics and Reboot are excluded from this measurement.)
OCPP response timeout:	5s	00:00:03	The response time for when waiting for an OCPP response message.
Response time RemoteStartTransaction:	5s	00:00:00	The response time for the RemoteStartTransaction message.

Test Configuration

Vendor	MODERNTEC Co., Ltd
DUT / SUT	Charging Station
Communication	JSON
Type	MC-IN60-1A-C
OCPP Software version	1.0.0
OCTT version	OCTT 1.6 v1.4.3

Hardware feature set	
Feature	**Configuration**
Socket(s) / connector(s)	Single
Fixed cable	<Yes>
Communication technology	Ethernet
RFID readers	Single

Non-OCPP Charge Point Configuration	
Configuration key	**Value**
<>	<>

All other relevant limits and non-OCPP settings that are relevant for the test laboratory and for the correct functioning of the CSMS:	
Limit / setting	**Value**
Device supports sending milliseconds in timestamps.	Yes

OCPP Charging Station Configuration	
Configuration key	**Value**
AllowOfflineTxForUnknownId	FALSE
AuthorizationCacheEnabled	TRUE
AuthorizeRemoteTxRequests	TRUE
BlinkRepeat	60
ClockAlignedDataInterval	60
ConnectionTimeOut	60
ConnectorPhaseRotation	-
ConnectorPhaseRotationMaxLength	-
GetConfigurationMaxKeys	20
HeartbeatInterval	60
LightIntensity	60
LocalAuthorizeOffline	TRUE
LocalPreAuthorize	FALSE
MaxEnergyOnInvalidId	60
MessageTimeout	-
MeterValuesAlignedData	-
MeterValuesAlignedDataMaxLength	20
MeterValuesSampledData	-
MeterValuesSampledDataMaxLength	20
MeterValueSampleInterval	15
MinimumStatusDuration	60
NumberOfConnectors	1
ResetRetries	0
StopTransactionMaxMeterValues	150
StopTransactionOnEVSideDisconnect	TRUE
StopTransactionOnInvalidId	FALSE
StopTxnAlignedData	-
StopTxnAlignedDataMaxLength	20
StopTxnSampledData	-
StopTxnSampledDataMaxLength	20
SupportedFeatureProfiles	Core,FirmwareManagement,LocalAuthListManagement,Reservation,SmartCharging,RemoteTrigger
SupportedFeatureProfilesMaxLength	-
TransactionMessageAttempts	0
TransactionMessageRetryInterval	60
UnlockConnectorOnEVSideDisconnect	FALSE
WebSocketPingInterval	60
LocalAuthListEnabled	FALSE
LocalAuthListMaxLength	60
SendLocalListMaxLength	60
ReserveConnectorZeroSupported	TRUE
ChargeProfileMaxStackLevel	60
ChargingScheduleAllowedChargingRateUnit	Ampere
ChargingScheduleMaxPeriods	60
ConnectorSwitch3to1PhaseSupported	FALSE
MaxChargingProfilesInstalled	60
SupportedFileTransferProtocols	http, https, ftp, ftps

Statement of Approval

Vendor		Date: 2023.07.13
Name	Seongdoo Kim	Signature
Company	MODERNTEC Co., Ltd	
Department	Representative Director	*Seongdoo Kim*
Position	Chief Executive Officer	
Location	Seoul, Korea	

Test laboratory		Date: 2023.07.13
Name	Philip YANG	Signature
Company	Korea Smart Grid Association	
Department	Quality Certification Center	
Position	Chief Researcher	
Location	Seoul, Korea	