OCPP 1.6 Subset Certificate



Certificate holder: EL-Electric

Certificate number: OCA.0016.0593.CS

Product type: Charging Station

Product designation: WEV-D100PM-C1B

OCPP Software version: 1.1.1.2

Hardware feature set as stated below

Certification date: December 7, 2023

This certificate attests that the above mentioned product successfully completed certification testing in conformance with the reference specification OCPP 1.6 – Edition 2 with OCPP 1.6 Errata sheet (v4.0 Release, 2019-10-23). The optional features of the protocol covered by this certificate can be found in the abstract of this certificate.

Test cases have been performed as described in the test report referred to below. The results and remarks can be found in the complete test report.

Applied tests	Performed by / on	Document evidence
Conformance testing according to the test specification referenced by the test report	Korea Smart Grid Association, December 7, 2023	(KSGA)EL-ELECTRIC_Test Report_WEV-D100PM-C1B_v1.5

The abstract of test report in the Annex is an integral part of this certificate. This certificate is valid from the Certification Date specified above. This certificate is only applicable to the product designation described above and permits the use of the OCPP logo as laid down in the OCA certification logo license agreement on this product only.

This certificate shall neither be tendered nor accepted by any party as a guarantee covering quality of a product which includes OCPP. The Open Charge Alliance, and/or its agents, including, inter-alia, test laboratories, disclaim liability for any damages or losses incurred by the certified company or by any other party resulting from reliance on the results of OCPP certification testing.

For the Open Charge Alliance:

Chairman



Abstract of test report

Test Result Summary

Test Report OCPP 1.6 Certification				
Test laboratory:	Korea Smart Grid Association			
Location:	Seoul, Korea			
Test execution location:	EL-Electric (Namyangju, Korea)			
Test Report Reference: KSGA-OCPP1.6TEST-229-2023				
Vendor name:	EL-Electric			
Device Under Test:	Charging Station			
Communication:	JSON			
OCPP Software version:	1.1.1.2			
Product designation:	WEV-D100PM-C1B			

Troduct designation: WEV-DIOOFWI-CID			
Test Result Summar	y for the ce	ertified functionalities	
Functionalities	OCPP 1.6 Certification Test Results		
Core	Pass	Basic Charging Station functionality for booting, authorization (incl. cache if available), configuration, transactions, remote control.	
Optional features			
Firmware Management	N/A	Support for (remote) firmware update management and diagnostic log file download.	
Smart Charging	N/A	Support for Smart Charging (all profile types, including stacking), to control charging.	
Reservation	N/A	Support for reservation of a connector of a Charging Station.	
Local Authorization List Manageme	N/A	Features to manage a local list in the charging station containing authorization data for whitelisting users.	
Remote Trigger	N/A	Support for remotely triggering messages that originate from a Charging Station. This can be used for resending messages or for getting the latest information from the Charging Station.	

Page 1 from 4



Performance Measurement Results

Name	PICS value	Measured value	Description
OCPP triggered function timeout:	60s	0:00:14	The response time for when waiting for an OCPP function with its corresponding request message. (Firmware update, Diagnostics and Reboot are excluded from this measurement.)
OCPP response timeout:	60s	00:00:08	The response time for when waiting for an OCPP response message.
Response time RemoteStartTransaction:	60s	00:00:00	The response time for the RemoteStartTransaction message.

Test Configuration

Vendor	EL-Electric
DUT / SUT	Charging Station
Communication	JSON
Type / model	DC100kW/WEV-D100PM-C1B
OCPP Software version	1.1.1.2
OCTT version	OCTT 1.6 v1.4.3

Hardware feature set			
Feature Configuration			
Socket(s) / connector(s)	Single		
Fixed cable	<yes></yes>		
Communication technology	Ethernet, Mobile network		
RFID readers	Single		

Non-OCPP Charge Point Configuration		
Configuration key Value		
<>		<>



OCPP Charging Station Configuration			
Configuration key	Value		
AllowOfflineTxForUnknownId	TRUE		
AuthorizationCacheEnabled	FALSE		
AuthorizeRemoteTxRequests	TRUE		
BlinkRepeat	0		
ClockAlignedDataInterval	0		
ConnectionTimeOut	60		
ConnectorPhaseRotation	Unknown		
ConnectorPhaseRotationMaxLength	0		
GetConfigurationMaxKeys	0		
HeartbeatInterval	60		
LightIntensity	0		
Local Authorize Offline	TRUE		
LocalPreAuthorize	FALSE		
MaxEnergyOnInvalidId	0		
MessageTimeout	0		
MeterValuesAlignedData	0		
	- 50		
MeterValuesAlignedDataMaxLength			
MeterValuesSampledData	Energy.Active.Import.Register		
MeterValuesSampledDataMaxLength	50		
MeterValueSampleInterval	20		
MinimumStatusDuration	0		
NumberOfConnectors	1		
ResetRetries	0		
StopTransactionMaxMeterValues	50		
StopTransactionOnEVSideDisconnect	TRUE		
StopTransactionOnInvalidId	TRUE		
StopTxnAlignedData	-		
StopTxnAlignedDataMaxLength	50		
StopTxnSampledData	-		
StopTxnSampledDataMaxLength	50		
SupportedFeatureProfiles	Core		
SupportedFeatureProfilesMaxLength	5		
TransactionMessageAttempts	0		
TransactionMessageRetryInterval	10		
UnlockConnectorOnEVSideDisconnect	FALSE		
WebSocketPingInterval	0		
LocalAuthListEnabled	-		
LocalAuthListMaxLength	-		
SendLocalListMaxLength	-		
ReserveConnectorZeroSupported	-		
ChargeProfileMaxStackLevel	-		
ChargingScheduleAllowedChargingRateUnit	-		
ChargingScheduleMaxPeriods	-		
ConnectorSwitch3to1PhaseSupported	-		
MaxChargingProfilesInstalled	-		
SupportedFileTransferProtocols	-		



Statement of Approval

Vendor		Date: 2023.12.07
Name	Park Jeonggeun	Signature
Company	EL-Electric	
Department	President	
Position	Chief Executive Officer	Ju/~1
Location	Namyangju, Korea	

Test laboratory			Date : 2023.12.07
Name	Philip YANG		Signature
Company	Korea Smart Grid Association		4
Department	Quality Certification Center		
Position	Chief Researcher		A.
Location	Seoul, Korea		,