# OCPP 1.6 Subset Certificate



Certificate holder:	PLINE MOTORS Co.,Ltd	
Certificate number:	OCA.0016.0631.CS	
Product type:	Charging Station	
Product designation:	NE-S7-C-IC OCPP Software version: A1.0 Hardware feature set as stated below	
Certification date:	January 19, 2024	

This certificate attests that the above mentioned product successfully completed certification testing in conformance with the reference specification OCPP 1.6 – Edition 2 with OCPP 1.6 Errata sheet (v4.0 Release, 2019-10-23). The optional features of the protocol covered by this certificate can be found in the abstract of this certificate.

Test cases have been performed as described in the test report referred to below. The results and remarks can be found in the complete test report.

Applied tests	Performed by / on	Document evidence
Conformance testing according to the test specification referenced by the test report	Korea Smart Grid Association, January 19, 2024	(KSGA)Plinemotors_Test Report_NE- S7-7-IC_v1.5

The abstract of test report in the Annex is an integral part of this certificate. This certificate is valid from the Certification Date specified above. This certificate is only applicable to the product designation described above and permits the use of the OCPP logo as laid down in the OCA certification logo license agreement on this product only.

This certificate shall neither be tendered nor accepted by any party as a guarantee covering quality of a product which includes OCPP. The Open Charge Alliance, and/or its agents, including, inter-alia, test laboratories, disclaim liability for any damages or losses incurred by the certified company or by any other party resulting from reliance on the results of OCPP certification testing.

For the Open Charge Alliance:

**ONOPH CARON** Chairman



## Abstract of test report

#### Test Result Summary

Test Report OCPP 1.6 Certification				
Test laboratory: Korea Smart Grid Association				
Location: Seoul, Korea				
Test execution location: KSGA Test Lab				
Test Report Reference: KSGA-OCPP1.6TEST-002-2024				
Vendor name: PLINE MOTORS Co.,Ltd				
Device Under Test: Charging Station				
Communication: JSON				
OCPP Software version: A1.0				
Product designation:	NE-S7-C-IC			

Test Result Summary	/ for the ce	ertified functionalities
Functionalities	OCPP 1.6 Certification Test Results	Description
Core	Pass	Basic Charging Station functionality for booting, authorization (incl. cache if available), configuration, transactions, remote control.
Optional features		
Firmware Management	N/A	Support for (remote) firmware update management and diagnostic log file download.
Smart Charging	N/A	Support for Smart Charging (all profile types, including stacking), to control charging.
Reservation	N/A	Support for reservation of a connector of a Charging Station.
Local Authorization List Management	N/A	Features to manage a local list in the charging station containing authorization data for whitelisting users.
Remote Trigger	N/A	Support for remotely triggering messages that originate from a Charging Station. This can be used for resending messages or for getting the latest information from the Charging Station.





#### Performance Measurement Results

Name	PICS value	Measured value	Description
OCPP triggered function timeout:	60s	00:00:18	The response time for when waiting for an OCPP function with its corresponding request message. (Firmware update, Diagnostics and Reboot are excluded from this measurement.)
OCPP response timeout:	10s	00:00:01	The response time for when waiting for an OCPP response message.
Response time RemoteStartTransaction:	10s	00:00:00	The response time for the RemoteStartTransaction message.

#### Test Configuration

Vendor	PLINE MOTORS Co.,Ltd		
DUT / SUT	Charging Station		
Communication	JSON		
Туре	NE-S7-C-IC		
OCPP Software version	A1.0		
OCTT version	OCTT 1.6 v1.4.3		

Hardware feature set					
Feature Configuration					
Socket(s) / connector(s)	Single				
Fixed cable	<yes></yes>				
Communication technology	Mobile network				
RFID readers	Single				
Non-OCPP Charge Point Configuration					
Configuration key Value					
<>	<>				

All other relevant limits and non-OCPP settings that are relevant for the test laboratory and for the correct functioning of the CSMS:

Limit / setting	Value	
Device supports sending milliseconds in	Yes	
timestamps.	105	

Certified

OCPP Charging Station Configuration				
Configuration key	Value			
AllowOfflineTxForUnknownId	-			
AuthorizationCacheEnabled	-			
AuthorizeRemoteTxRequests	TRUE			
BlinkRepeat	-			
ClockAlignedDataInterval	86400			
ConnectionTimeOut	30			
ConnectorPhaseRotation	Unknown			
ConnectorPhaseRotationMaxLength	-			
GetConfigurationMaxKeys	20			
HeartbeatInterval	300			
LightIntensity	-			
LocalAuthorizeOffline	FALSE			
LocalPreAuthorize	FALSE			
MaxEnergyOnInvalidId	-			
MessageTimeout	-			
MeterValuesAlignedData	-			
MeterValuesAlignedDataMaxLength	7			
MeterValuesSampledData	-			
MeterValuesSampledData MeterValuesSampledDataMaxLength	7			
MeterValueSampleInterval	60			
MinimumStatusDuration	-			
NumberOfConnectors	- 1			
ResetRetries	3			
	9999999999999			
StopTransactionMaxMeterValues StopTransactionOnEVSideDisconnect	TRUE			
StopTransactionOnInvalidId	TRUE			
StopTxnAlignedData	TRUE			
StopTxnAlignedData StopTxnAlignedDataMaxLength	- 12			
StopTxnSampledData	-			
StopTxnSampledDataMaxLength	- 12			
SupportedFeatureProfiles				
Supported Feature Profiles MaxLength	Core			
TransactionMessageAttempts	1			
TransactionMessageRetryInterval	30			
UnlockConnectorOnEVSideDisconnect	FALSE			
WebSocketPingInterval	60			
LocalAuthListEnabled	-			
LocalAuthListMaxLength	-			
SendLocalListMaxLength	-			
ReserveConnectorZeroSupported	-			
ChargeProfileMaxStackLevel	-			
ChargingScheduleAllowedChargingRateUnit	-			
ChargingScheduleMaxPeriods	-			
ConnectorSwitch3to1PhaseSupported	-			
MaxChargingProfilesInstalled	-			
SupportedFileTransferProtocols	-			

Page **3** from **4** 



### Statement of Approval

Vendor		Date: 2024.01.19
Name	Hobum Hong	Signature
Company	PLINE MOTORS Co.,Ltd	$\square$
Department Quality Assurance Team		
Position	Team Manager	1/12
Location	Seoul, Korea	

Test laboratory		Date: 2024.01.19
Name Philip YANG		Signature
Company Korea Smart Grid Association		4
Department Quality Certification Center		
Position	Chief Researcher	A.
Location	Seoul, Korea	

Page **4** from **4**