



**Certificate Holder:** Jiangsu Tellus Power Co. Ltd.  
**Certificate Number:** OCA.0016.1246.CS  
**Product Type:** Charging Station  
**Product Designation:** TP-EVPD-180KW  
**Firmware Version:** 250715.0768  
**Certification Date:** June 9, 2026

This certificate attests that the above mentioned product successfully completed certification testing in conformance with the reference specification OCPP 1.6 (Edition 2 FINAL, 2017-09-28 including Errata 2025-04) and Security Whitepaper Edition 4 (Improved security for OCPP 1.6-J v1.4, 2026-02-05). The optional OCPP protocol features that are covered by this certificate can be found in the Abstract of the Test Report that is part of this certificate.

Test cases have been performed as described in the test report referred to below. The results and remarks can be found in this complete test report.

Applied	Performed by / On	Document Evidence
Conformance testing according to the test specification referenced by the test report	DEKRA CERTIFICATION INC. May 26, 2026	Tellus_OCPP-1.6-PICS-CS-3.0.6_signed

The abstract of test report is an integral part of this certificate. This certificate is valid from the Certification Date specified above. This certificate is only applicable to the product designation described above and permits the use of the OCPP logo as laid down in the OCA certification logo license agreement on this product only.

This certificate shall neither be tendered nor accepted by any party as a guarantee covering quality of a product which includes OCPP. The Open Charge Alliance, and/or its agents, including, inter-alia, test laboratories, disclaim liability for any damages or losses incurred by the certified company or by any other party resulting from reliance on the results of OCPP certification testing.

For the Open Charge Alliance:

**ONOPH CARON**  
Chairman

## Abstract of the Test Report

### Test Report OCPP 1.6 Certification

<b>Test laboratory:</b>	<b>DEKRA CERTIFICATION INC.</b>
Location:	Sterling, Virginia, USA
Test Report Reference:	0596ORCO.001
<b>Product Designation:</b>	<b>TP-EVPD-180KW</b>
Vendor name:	Jiangsu Tellus Power Co. Ltd.
Device Under Test:	Charging Station
Firmware Version:	250715.0768
Config ID:	I2D2C896-8DB8445D

### Test Result Summary for the Certified Functionalities

Certification Profile	Test Result	Description
Core	Pass	Basic Charging Station, functionality for booting, authorization, configuration, transactions, remote control, secure firmware updates and Security Profile 2.
Advanced Security	Pass	Support for TLS with client authentication.
Smart Charging	Pass	Support for Smart Charging, to control charging.

## Hardware Feature Set

The Hardware Feature set is the actual set of relevant hardware properties of the product tested, that influence the OCPP messaging behavior. In the table below you can see for each hardware feature relevant for OCPP whether this is applicable for this product.

ID	Feature	Supported / Present
HFS-1	Has a detachable cable	No
HFS-2	Has a fixed cable	Yes
HFS-3	Has AC support	No
HFS-4	Has DC support	Yes
HFS-5	Has 1 phase support	No
HFS-6	Has 2 phase support	No
HFS-7	Has 3 phase support	No
HFS-8	No. Connectors	2
HFS-9	Communication technology	Ethernet, Mobile network, WiFi
HFS-10	RFID readers	Single
HFS-11	DC power level	180

Connector	Current	Phases	Type	Cable Type
1	DC		cCCSI	Fixed Cable
2	DC		cNACS	Fixed Cable



## Optional Features

The OCPP specification contains many implementation options that can be selected by a vendor, often in the form of optional message fields or configuration variables, that can be used to support advanced functions. Whereas the certification profiles determine which OCPP functionality is implemented, the features describe how much of a certain functionality in a profile has been implemented. The tables below indicate per certification profiles, for each available optional feature within this profile, whether this has been implemented in this product and tested for conformance or not.

### Core

ID	Core Features	Supported / Present
C-01	Support for offline authorization of transactions	Yes
C-02	Support for allowing Offline Authorization for Unknown Ids	Yes
C-03	Support for maximizing energy for invalid ids	Yes
C-04	Authorization Cache	Yes
C-05	Support to limit StatusNotifications	No
C-06	Authorization status after cable disconnected on EV side	
C-06.1	Support for maintaining authorization when cable disconnected on EV side	Yes
C-06.2	Support for not maintaining authorization when cable disconnected on EV side	Yes
C-07	Support for local start	Yes
C-08	Support for local stop	Yes
C-10	Unlocking of connector when cable disconnected on EV side	
C-10.1	Support for unlocking connector when cable disconnected on EV side	No
C-10.2	Support for not unlocking when cable disconnected on EV side	Yes
C-11	Support for Security Profile 1: Unsecured Transport with Basic Authentication	Yes

ID	Metervalues	Tested During Certification	Supported According to Vendor
C-09	Supported MeterValue Measurands		

ID	Metervalues	Tested During Certification	Supported According to Vendor
C-09.1	MeterValuesSampled Data	SoC Current.Offered Power.Active.Import Temperature Energy.Active.Import.Register Current.Import Power.Offered Voltage	SoC Energy.Active.Import.Register Current.Import Current.Offered Voltage Power.Active.Import Power.Offered Temperature
C-09.2	MeterValuesAligned Data	SoC Current.Offered Power.Active.Import Temperature Energy.Active.Import.Register Current.Import Power.Offered Voltage	SoC Energy.Active.Import.Register Current.Import Current.Offered Voltage Power.Active.Import Power.Offered Temperature

ID	Cipher Suites	Supported / Present
C-12	Supported Cipher Suites	TLS_RSA_WITH_AES_128_GCM_SHA256 TLS_RSA_WITH_AES_256_GCM_SHA384

ID	Local Authorization List Management	Supported / Present
LA-0	Support for Local Authorization List Management	Yes

ID	Remote Trigger	Supported / Present
RT-0	Support for Remote Trigger	Yes

ID	Reservations	Supported / Present
R-0	Support for Reservations	Yes
R-1	Support reservations of entire Charging Station	Yes

## Smart Charging

ID	Certification Profile: Smart Charging	Supported / Present
SC-1	Supported charging rate units	
SC-1.1	A	Yes
SC-1.2	W	Yes

### Additional Questions

The table below lists a number of questions that are needed for determining the complete list of conformance test for this product.

ID	Additional Questions for Lab Testing	Answer
AQ-1	Can the last CentralSystemRootCertificate can be removed?	No
AQ-2	Does the Charging Station have a cable lock, which prevents the EV driver to connect the EV and EVSE before authorization?	No
AQ-3	Can the last ChargePointCertificate be removed?	No
AQ-4	Is your Charging Station able to download firmware while there is an ongoing transaction?	Yes
AQ-5	Does your Charging Station enforce a selection of EVSE prior to authorization?	No
AQ-6	Does your Charging Station support charging an EV using IEC 61851-1?	No
AQ-7	Reporting of StopTransaction after power loss	
AQ-7.1	Charge Point configured to report StopTransaction before going down.	No
AQ-7.2	Charge Point configured to report StopTransaction after going down and being back online again.	Yes
AQ-9	Does your Charging Station have at least one connector with an mechanized locking mechanism on Charging Station side?	No
AQ-11	Does your Charging Station support an authorization method, that does not rely on the communication between EV and Charging Station?	Yes

## Other Relevant Settings

The table below lists a number of settings that are needed for configuring the test setup for the conformance test for this product.

ID	Limit / Setting	Value
ORS-1	GetConfigurationMaxKeys	71
ORS-2	MeterValuesAlignedDataMaxLength	10
ORS-3	MeterValuesSampledDataMaxLength	10
ORS-4	Minimum MeterValueSampleInterval supported	1
ORS-5	Maximum MeterValueSampleInterval supported	300
ORS-6	Minimum HeartbeatInterval supported	1
ORS-7	Maximum HeartbeatInterval supported	300
ORS-8	StopTransactionMaxMeterValues	10
ORS-9	StopTxnAlignedDataMaxLength	10
ORS-10	StopTxnSampledDataMaxLength	10
ORS-11	WebSocketPingInterval	5
ORS-12	LocalAuthListMaxLength	500
ORS-13	SendLocalListMaxLength	500
ORS-17	CertificateSignedMaxChainSize	10000
ORS-18	CertificateStoreMaxLength	8192

ID	Certification Profile: Smart Charging	Value
ORS-14	ChargingProfileMaxStackLevel	2
ORS-15	ChargingScheduleMaxPeriods	12
ORS-19	MaxChargingProfilesInstalled	3

ID	Firmware Management Settings	Value
ORS-16	Supported file transfer protocols	HTTP HTTPS FTP FTPS

## Additional Network Communication Ports

Description	Protocol	Network Port	Direction	Secured
Used to connect to EMS energy management system	https	443	Inbound	Yes
For local communication of devices	TCP	8001	Inbound	Yes
Used for inter-process message push	MQTT	1883	Inbound	Yes
For remote equipment maintenance	ssh	22	Inbound	Yes

## Vendor Specific Settings

The table below should contain all relevant non-OCPP settings of the System Under Test that are relevant for the test laboratory and for the correct OCPP-compliant functioning :

Configuration Setting	Configured Value	Description
PlugInChargeMode	False	Whether to support the plug-in gun free charging
PlugInMacidAuth	False	Whether to start charging using EV MAC address
RebootSystemEnable	False	Whether to restart the system and reconnect to the network when offline
SecurityKeyType	rsa	Set the encryption algorithm type: "rsa","dsa","ec"
SecurityDigest	SHA256	Set the digital Digest algorithm "sha256", "sha384", "sha512", "sha3-256", "sha3-512", "shake256", "sha1", "md5"
DefaultPrice	"priceText\":"0.15 \$/kWh, idle fee after charging: 1 \$/hr\","priceTextOffline\":"The station is offline. Charging is possible for 0.15\$/kWh.\","charging Price\":"{\kWhPrice\":"0.15\","hourPrice\":"0,\flatFee\":"0	Default charging price

## Performance Measurement Result

The tables below shows the list of key performance indicators that are measured during the conformance test. The first table indicates the values that the vendor indicates that are valid maximum values for this product. The second table lists the actual performance measurements during the tests performed in a controlled environment.


Name	Max Value	Unit	Description
OCPP response timeout	30	seconds	The timeout used for exchanging OCPP response messages. Messages to the DUT can be handled within this timeout.
OCPP triggered function timeout	30	seconds	The timeout used for when waiting for an OCPP function with its corresponding request message. Messages to the DUT can be handled within this timeout. This value excludes firmware, diagnostics and rebooting
Transaction authorization time by RemoteStartTransaction	40	seconds	The time between the RemoteStartTransaction.req message and the corresponding StartTransaction.req. Only cases where the RemoteStartTransaction immediately results in an authorization followed by a StartTransaction.req are included.
Transaction authorization end time by RemoteStopTransaction	30	seconds	The time between the RemoteStopTransaction.req message and the corresponding StopTransaction.req. Only cases where the RemoteStopTransaction immediately results in an end of the authorization followed by a StopTransaction.req are included.

Name	Min Value	Max Value	Average Value	Unit
OCPP response timeout	0.12	4.93	0.20	seconds
OCPP triggered function timeout	0.14	0.55	0.28	seconds
Transaction authorization time by RemoteStartTransaction	31.99	31.99	31.99	seconds
Transaction authorization end time by RemoteStopTransaction	3.09	3.30	3.17	seconds

Communication technology used during performance measurement	Ethernet
--	----------

## Statement of Approval

Vendor		
Name	Hongbin Song	Date: 2026-05-28
Company	Jiangsu Tellus Power Co. Ltd.	Signature:
Department	R&D	
Position	R&D General Manager	
Location	Jiangsu China	

Test Laboratory		
Name	Avinash Koduri	Date: 2026-06-09
Name reviewer	Gonzalo Casado	Signature:
Company	DEKRA CERTIFICATION INC.	
Department	Connectivity & E-Mobility	
Position	Director	
Location	Sterling, Virginia, USA	

OCTT Version	Release_2026-04
OCTT Instance ID	97c49552d423d6e947b631fce50d2b13
Firmware image hash	952a14887aa70653fc8d49433a25d22319bcl69b54af8ec7487a524d24a6770a